OFFICE OF THE SECRETARY, EXHIBITION COMMITTEE, GOVERNMENT SOAP FACTORY, BANGALORE.

Notice dated 29th June 1933.

Applications for running an Indan Restaurant or European Restaurant in the Exhibition Grounds, Mysore, for one month from 10th September 1933, will be received by the Secretary, Exhibition Committee on or before the 25th August 1933.

The applications should be sent by Registered post and be accompanied by a cash deposit of Rs. 50 as earnest money which will be returned in the case of those whose applications are not accepted.

A schedule of rates for the various kinds of refreshments and meals should accompany each application.

The applicants should state the highest amount that they are prepared to pay for the right of running the Restaurant in the Exhibition Grounds.

Final acceptance of the application will rest with the Chairman who reserves the right to accept or reject any application without assigning reasons therefor.

The successful applicant should execute within three days an agreement that he would sell wholesome foodstuff prepared in unadulterated ghee at the rates approved by the Committee and would abide by certain other conditions mentioned in the agreement.

The successful applicant should pay 50 per cent of the amount tendered by him at the time of executing the agreement and the balance before the close of the Exhibition; failing which, the earnest money deposited will be forfeited and the right given away to some other applicant at the defaulter's risk. He shall have no claim to any surplus but shall be liable for the loss arising therefrom.

S. G. SASTRY,
Secretary,
Exhibition Committee.

MYSORE RAILWAYS.

MYSORE DIVISION—(OPEN LINES).

Notification, dated 30*th June* 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Open Line Division, Mysore Railways, Mysore, up to 4 P.M. on Monday the 24th July 1933, from contractors who are willing to do the work of extending the existing Foundry Shop to be used as Pattern Shop in the Central Workshop area.

2. Every tender must be accompanied by an earnest money of Rs. 200 which should be paid to the Auditor, Mysore Railways, Mysore and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms which can be obtained from the Senior Executive Engineer, Mysore Railways, Mysore, on payment of rupee one which amount is not refundable under any circumstances.

4. Tenders which give rates, as per estimate rates or so much per cent above or below estimate rates, will not be considered. The rates should be noted both in figures and words.

5 The name of the accepted tenderer will be posted on the Notice Board of the Senior Executive Engineer's Office as soon as it is approved by the Superintendent, Way and Works Mysore Railways. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of while that of the successful tenderer will be accepted as part payment towards the security deposit due as per Para 7 *infra*.

7. The successful tenderer should deposit with the Auditor, Mysore Railways, Mysore, before he signs the Schedule Agreement five per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the agreement.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, for any or all the tenders.

9. Successful tenderers should execute within eight days of the date of notification of acceptance of tenders, the usual Railway Schedule Agreement. Failure to comply with this condition will render the contract null and void and the earnest money forfeited.

10. Work should be started within two weeks from the date of acceptance of tender and completed within 12 weeks from the date of orders to start the work. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

11. The time limit specified in Para 10 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his five per cent deposit amount not as a [redacted] accordingly.

12. Plans and specifications and other details of work to be done are available for inspection in the Senior Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

13. In all matters of dispute regarding rates, measurements, quality of work, etc., an in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore Railways, will be final and legally binding.

14. Contractors should make their own arrangements for water required for the work and Departmental water will not be supplied.

SCHEDULE.

Sl. No.	Particulars	Per	Quantity
1	Earthwork ; lowering ground and excavating for foundation in all soils including hard rock by wedges except blasting conveying the spoil to bank including a lead of 1500 feet.	1000 c.ft.	7950
2	Concrete, broken stone in sand mortar ...	100 c.ft.	250
3	Dismantling stone masonry	100 c.ft.	141
4	Stone masonry in sand mortar with released stones ...	100 c. ft.	70
5	Size stone in sand mortar (coursed rubble first sort) ...	100 c.ft.	2311
6	Supplying and fixing in sand mortar, burnt stone slabs 6" thick dressed.	S.ft.	156
7	Dismantling, hoisting and fixing burnt stone slabs in sand mortar.	,,	36
8	Conveying, hoisting and fixing in position R. S. Beams including drilling holes in R. S. Beams and anchor plates and fixing of holding-down bolts and anchor plates	Cwt.	27·1
9	Dismantling masonry for insertion of R. S. Beams and bearing slabs and rebuilding masonry	Each R.S. Beam	3
10	Teakwood wrought and put up including two coats of wood oiling.	C.ft.	99·48
11	Roofing with pucca terrace 9" thick complete including chunam plastering.	Sqr.	924
12	Cornice 9" thick two courses of burnt stone slabs dressed with cement pointing including hoisting and fixing the slabs in sand mortar.	R. ft.	44
13	Dismantling cornice 9" thick two courses of burnt stone slabs, hoisting and fixing the same in sand mortar.	,,	23
14	Coping slabs 6" thick two lines dressed and chamfered including cement pointing.	S.ft.	77
15	Dismantling coping slabs, hoisting and fixing the same in sand mortar including cement pointing.	,,	39
16	Teakwood windows with iron bars and panelled shutters outside and glazed shutters inside as per approved design.	,,	80
17	Teakwood ventilators with glazed shutters as per approved design.	,,	30
18	Removing teakwood windows, converting it into a door by fixing teakwood panelled shutters and fixing the same (as per approved design).	,,	100
19	Removing teakwood windows and refixing them ...	Each	2
20	Cement pointing	Sqr.	24·56
21	Flooring with burnt stone slabs 4" thick dressed over a bed of 6" thick concrete (broken stone in sand mortar) including cement pointing.	,,	840
22	Removing, and cutting and refixing Cast Iron Down Water pipes including fixing of wooden supports and straps.	R.ft.	32
23	Silicate painting two coats	Sqr.	684
24	Burnt brick in sand mortar	100 c.ft.	17
25	Chunam plastering	Sqr.	907
26	Racking the joint above the terrace roof, inserting galvanised iron plain sheets and making the joint water tight.	R. ft.	44
27	Dressing corners at ends of walls and jambs of windows, doors, etc.	,,	167